Sheet2

BOQ

| Sr.No. | Description of Item | Qty. | Unit | Rate | Amount |
|--------|---|------|------|------|--------|
| 1 | Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. (Old CC paver blocks shall be supplied by the department free of cost). (This includes removing of pavers also). | 250 | Sqm | | |
| | Total | | | | |

Contractor