



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान मोहाली

(मानव संसाधन विकास मंत्रालय का एक स्वायत्त संस्थान, भारत सरकार के अधीन)

सैक्टर-81, नॉलेज सिटी, पो.ओ. मनौली, एस.ए.एस. नगर, मोहाली पंजाब-140306

INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH MOHALI

(Estd. By Ministry of Human Resource Development, Govt. of India)

Sector – 81, Knowledge City, P.O. Manauli, S.A.S. Nagar, Mohali, Punjab -140 306

Executive Engineer cum Estate Officer

Telefax No. : 0172-2240110

IISER/18-19/EE-EO/

Date: 16.11.2018

To

Sub: Repair work on the terrace of LHC auditorium, AB-1, AB-2 & road gully at IISER Mohali, Sector-81, SAS Nagar, Mohali- reg.

Dear Sir,

You are requested to give your competitive rates by 1500 hrs on 26.11.2018 as per the below:

Sr. No.	Description of item	Qty	Unit	Rate	Amount
1/ 4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
4.1.8	1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	1	cum		
2/6.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:				
6.1.2	Cement mortar 1:6 (1 cement : 6 coarse sand)	1	cum		
3/13.1	12 mm cement plaster of mix :				

13.1.2	1:6 (1 cement: 6 fine sand)	128	sqm		
4/ 14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead :				
14.1.1	With cement mortar 1:4 (1 cement : 4 fine sand)	20	sqm		
4/ 16.63	Providing, laying and making kerb channel 30 cm wide and 50 mm thick with cement concrete 1:3:6 (1 cement: 3 coarse sand:6 graded stone aggregate 20 mm nominal size) over 75mm bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including finishing the top smooth etc. complete and as per direction of Engineer-in-charge.	28	sqm		
	Total				

GENERAL CONDITIONS OF THE RFQ

1. The rates shall be quoted in the enclosed schedule of quantities and duly signed by the contractor.
2. Rates to be inclusive of GST, etc.
3. Rates to remain firm during the duration of work as well as for the extended period, if any. No escalation in rates will be allowed in any circumstances.
4. The contractor shall comply with all statutory requirements in respect of said work.
5. The quantity can be increase or decrease.
6. The work shall be for the period of three weeks to be reckoned from the day of issue of award letter.
7. EMD amounting to Rs.1,100/- in favour of Registrar IISER, Mohali payable at Mohali.
8. Penalty of 0.5% per week shall be imposed for delay in work.

Sd/-
Executive Engineer