

BOQ

Sub: Fabrication and installation MS staircase at different locations in the campus

Sr. No.	DSR 2018	Description of Items	Qty	Unit	Rate	Amount
1	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	4.1.6	1:3:6 (1 Cement : 3 coarse sand (zone-III): 6 graded stone aggregate 40 mm nominal size)	1	cum		
2	10.16	Steel work in built up tubular trusses including cutting, hoisting fixing in position and applying a priming coat of approved steel primer, welded and bolted including special shaped washers etc. Complete.				
	10.16.1	Hot finished welded type tubes.	300	kg		
3	10.25	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
	10.25.1	In stringers, treads, landings etc. of stair cases including use of chequered plate wherever required, all complete.	150	Kg		
	13.1	12 mm cement plaster of mix :				
	13.1.2	1:6 (1 cement: 6 fine sand)	10	sqm		
	13.31	Pointing on brick work or brick flooring with cement mortar 1:3 (1 cement : 3 fine sand):				
	13.31.1	Flush / Ruled/ Struck or weathered pointing	20	sqm		
		Total				

Contractor