

## BOQ

Sub: Laying of Cable &amp; Feeder Pillar for STP of Hostel 6&amp;8 at IISER Mohali

Sno	Description	Qty	Unit	Rate	Amount
1	Supply & Laying of 3.5 core Al Ar.95mmsq Cable including Clamps, hardware. Excavation & back filling of cable trench with bricks & Termination of Cable.	225	Mtr.		
2	Supply & fixing of outdoor 160Amp 4 poles 25KA CRC sheet weather proof powered coated feeder pillar panel with 3 no. 100A O/G MCCB.	1	No		
3	Supplying, and fixing of 600x600x6 mm Earth pit char coal salt watering pipe main hole cover per IS 3043	2	No		
4	Supply and laying GI hot dip galvanized strip 25x6 mm with bolt clamp etc.	30	Mtr.		
	Total				

Contractor