

## BOQ

Sub: Connecting Animal House with Academic Block-I at IISER Mohali

Sr.no / DSR 2014	Description	Qty	Unit	Rate	Amount
1/ 2.2	Earth work in rough excavation, banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead up to 50 m and lift up to 1.5 m :				
2.2.1	All kind of soil	1	cum		
2/ 4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
4.1.3	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size	1.00	cum		
3/ 10.26	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing and staircase railing including applying a priming coat of approved steel primer.				
10.26.1	M.S. tube.	480.00	kg		
4/ 13.61	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
13.61.1	Two or more coats on new work	40.00	sqm		
5/ 15.7	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.				
15.7.4	In cement mortar	0.50	cum		
6/ NS	P/f of 6 mm polycarbonate muyltiwall white/coloured sheet including aluminum beading and rubber all complete as per direction of Engineer in Charge.	47.00	sqm		
	Total				

Contractor