BOQ

Sub- Setting up of tissue culture lab at IISER Mohali

S. No	DSR Ref	Description of Items	Qty	Unit	Rate	Amount
1	NS	Fixing of Stainless sink with tap along with granite slab (to be provided by the Institute) and connection including CPVC 1/4" piping including cutting the top to accommodate sink and powder coating of the whole unit	1	nos		
2	NS	Providing and fixing of over head cabinet made up of 0.8 mm thick CRCA sheet and powder coated of 50 micron over the CRCA sheet with one shelve 2 feet height and 1.3" deep with shutter, SS handles and lock approved shade (granite to be provided by the Institute)		sqft		
3	NS	Providing and fixing of steel unit made up of 0.8mm thick CRCA sheet with cabinet, frame to be made up of 25x25mm square pipe and powder coating of 50 micron with approved shade (granite to be provided by the Institute)	105.00	sqft		
4	NS	Providing and fixing of steel unit made up of 0.8mm thick CRCA sheet without cabinet, frame to be made up of 25x25mm square pipeand powder coating of 50 micron with approved shade	70	sqft		
5	NS	P/f of 5mm PVDF ACP sheet single side lamination in partitions with neoprene all complete as per direction of Engineer-in-charge.	30.00	sqm		
6	21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing and paneling to be paid for separately):				
	21.1.1.1	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	240.00	kg		
7	21.3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item):				
	21.3.2	With float glass panes of 5.00 mm thickness	10.00	sqm		
		Total				

Contractor