

## Sheet2

## BOQ

Sub: Flooring in Dr Ram Yadav's lab in AB-2 at IISER Mohali

S.No.	Discription of item	Qty	Unit	Rate	Amount
1/ 11.26	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) :				
11.26.1	25 mm thick	180	sqm		
	Total				

Contractor