

**BOQ****Pavement leading to service corridor in CAF**

<b>S.No.</b>	<b>DSR Ref</b>	<b>Description</b>	<b>Unit</b>	<b>Qty.</b>	<b>Rate</b>	<b>Amount</b>
1	6.44	Brick edging 7cm wide 11.4 cm deep to plinth protection with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 including grouting with cement mortar 1:4 (1 cement : 4 fine sand).	mtr	135.00		
2	13.8	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	sqm	15.00		
3	14.45	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :				
	14.45.1	Old work (one or more coats)	sqm	20.00		
4	NS	Providing and laying 60mm thick factory made cement concrete interlocking prepolished rubber moulded paver block of M -35 grade made by block making machine with strong vibratory compaction and of approved size and design/ shape laid in required colour and pattern over and including 20-30mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	Sqm	145		
5		Providing and laying factory manufactured hydraulically pressed precast PCC kerb of mix M-25 of cross section 300 mm x 300 mm x 150 mm in position including cement pointing with cement mortar 1:2 (1 cement : 2 coarse sand) complete in all respect to the entire satisfaction of the Engineer Incharge.	mtr	20		
6	NS	Dismateling and refixing of sign board of size 5'x6' and 3'x3'in PCC 1:2:4 all complete and as desired	mtr	1		
		<b>Total</b>				

Contractor