

BOQ

Sub: P/f of luminaries in Hostels.

Sr.no	Description of Item	Qty.	Unit	Rate	Amount
1/1.17	Supplying and drawing following sizes of FR PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required, Make: Polycab, Havells, Anchor, Finolex.				
1.17.2	2 X 1.5 Sq. mm	2100	mtrs		
2/1.28	Supplying and Fixing following size modular base & cover plate on existing modular box as required, Make: ABB,L&T,Anchor Roma				
1.28.1	2 Module	180	nos		
3/1.24	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. Make : ABB,L& T,Anchor Roma				
1.24.1	5/6 amps switch	360	nos		
4/NS	Supplying and Fixing PVC Trunking on the wall with base i/c. accessories etc. as required.				
a)	25 X 10 mm	2100	mtrs		
5/NS	Supplying and Fixing following size PVC modular box as required, Make: ABB,L&T,Anchor Roma				
a)	2 Module	180	nos		
6/NS	P/f of LED batten tube light fitting of 9W on the wall complete with connections, interconnections, testing etc. Make : CG cat. No. LCTLP 10-CDL or eq in Philips/Wipro.	360	nos		
	Total				

Contractor