

BOQ

Brick edging on both sides of path connecting AB-1 to AB-2 and Informatics at IISER Mohali

S.No.	DSR Ref	Description	Unit	Qty.	Rate	Amount
1	6.44	Brick edging 7cm wide 11.4 cm deep to plinth protection with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 including grouting with cement mortar 1:4 (1 cement : 4 fine sand).	mtr	975.00		
2	NS/ 16.83	Taking out existing paver blocks from footpath/ central verge, including removal of rubbish, etc., disposal of unserviceable material to the dumping ground, leveling the area and stacking the unserviceable material within 50 mtr lead as per direction of Engineer-in-Charge	sqm	300		
3	NS/ 16.84	Laying old cement concrete grass paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 25 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. (Old CC paver blocks shall be supplied by the department free of cost).	sqm	300		
Grand Total						

Contractor