

BOQ

Sub: P/f of canopy at IISER, Mohali

Sr. No.	Description of Items	Qty	Unit	Rate	Amount
1	P/f of canopy made up of structural steel (MS I-section, channel, base plate, angle purlin etc. total weight 1950 kg) with fibre profile sheet at the top with necessary civil work such as painting & priming over structural steel, grouting of structural steel column in 1:2:4, raised kota flooring having kota 18- 20mm, raised 450mm from the ground level, side full brick wall 230mm with PCC 1:5:10 at the base, and provisions for electrical fixtures like conduiting, wiring, etc(fixtures will be installed by the Institute. all complete as per the drawing attached and direction of Engineer-in-Charge	1	nos		
	Total				

Contractor