BOQ Sub: Setting up of labs with ACP sheet clading, partitions , flooring, structural steel hanging arrangements

Sr. No.	Description of Items	Qty	Unit	Rate	Amount
	P/f of 5mm PVDF ACP sheet in walls & ceilings with screws				
1/ N.S	to seal it proper all complete as per direction of Engineer-in-	240	sqm		
	charge.				
2/ NS	Grinding of Kota stone flooring	100	sqm		
	Providing and fixing IS : 12817 marked stainless steel butt				
3/9.71	hinges (heavy weight) with stainless steel screws etc. complete :				
9.71.2	100x60x2.50 mm	9.00	each		
4/0 74	Providing and fixing bright finished brass tower bolts (barrel				
4/9.74	type) with necessary screws etc. complete :				
9.74.3		3.00	each		
	Providing and fixing bright finished brass 100 mm mortice latch				
	and lock with 6 levers and a pair of lever handles with necessary				
5/9.76	screws etc. complete (best make of approved quality).	3.00	each		
	sere we etc. comprete (best make or approved quanty).				
	Providing and fixing IS : 3564 marked Aluminium die cast body				
6/083	tubular type universal hydraulic door closer with necessary	3.00	each		
0/ 7.05	accessories and screws etc. complete.	5.00	Cach		
	Providing and fixing aluminium hanging floor door stopper ISI				
7/ 9.101	marked anodised (anodic coating not less than grade AC 10 as				
	per IS : 1868) transparent or dyed to required colour and shade				
0 101 0	with necessary screws etc. complete.	2.00	1		
9.101.2	Twin rubber stopper	3.00	each		
8/ 13.41	Distempering with oil bound washable distemper of approved				
	brand and manufacture to give an even shade				
13.41.1	New work (two or more coats) over and including priming coat	500	sqm		
	with cement primer.				
	Providing and applying white cement based putty of average				
9/ 13.8	thickness 1 mm, of approved brand and manufacturer, over the	100	sqm		
77 15.0	plastered wall surface to prepare the surface even and smooth	100	Sqiii		
	complete.				
	Removing dry or oil bound distemper, water proofing cement				
10/ 14.40	paint and the like by scrapping, sand papering and preparing the	200	aam		
10/ 14.40	surface smooth including necessary repairs to scratches etc.	200	sqm		
	Complete.				
	Providing and laying Ceramic glazed floor tiles 300x300				
	mm (thickness to be specified by the manufacturer) of 1st				
	quality conforming to IS : 15622 of approved make in				
	colours such as White, Ivory, Grey, Fume Red Brown,				
11/11.3	laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4	115	sqm		
	Coarse sand) including pointing the joints with white				
	cement and matching pigment etc., complete.				
	P/f of 5mm PVDF ACP sheet single side lamination in				
17/ NG	-	170	sam		
12/ 183	partitions with neoprene all complete as per direction of	170	sqm		
	Engineer-in-charge. Steel work welded in built up sections/ framed work				
13/ 10.2	Steel work welded in built up sections/ framed work				
	including cutting, hoisting, fixing in position and applying				
	a priming coat of approved steel primer using structural				
	steel etc. as required.				
10.25.2	In gratings, frames, guard bar, ladder, railings, brackets,	150	kg		
_ ~ , _ / , _	gates and similar works.		2		

11.41.2	Providing and laying polished vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS : 15622 of approved make in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete.	225	sqm		
15/ 18.10	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc.				
18.10.2	20 mm dia. nominal bore	10	mtr		
18.10.3	25 mm dia. nominal bore	25	mtr		
16/ 21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately):				
21.1.1	For fixed portion				
21.1.1. 2	Powder coated aluminium (minimum thickness of powder coating 50 micron)	1225.00	kg		
21.1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of PVC / neoprene gasket required (Fittings shall be paid for separately).				
21.1.2. 2	Powder coated aluminium (minimum thickness of powder coating 50 micron)	85.00	Kg		
17/ NS	P/f of solid 60 mm thick double skin Clean Room wall panels made up of 0.6mm GI powder coated sheet, infill material as puff having density of 40 kg/m3 with all required accessories like C type floor track, top channel, male female channel, Silicon sealant and fishes for grouting, etc all complete as per manufacturer specifications at all heights and as per direction of Engineer-in-Charge	70.00	sqm		
18/ NS	P/f of solid doors of size 7'x4', 60 mm thick double skin Clean Room wall panels made up of 0.6mm GI powder coated sheet, infill material as puff having density of 40 kg/m3 with all required accessories like C type floor track, top channel, male female channel, Silicon sealant and fishes for grouting, etc all complete as per manufacturer specifications at all heights and as per direction of Engineer-in-Charge	3.00	sqm		
19/ NS	P/f of 12 mm thick toughened glass for partition and making necessary holes for the accessories, etc (assesories will be paid extra)	50.00	sqm		

20/ NS	P/f of one way spider for ceiling/wall OSP A22 of MAKE OZONE/DORMA/DLINE	6.00	Nos	
21/183	IOZONE/DORMA/DLINE	12.00	Nos	
22/ NS	P/ffixed bolt (flat head) OSP FB FL of MAKE OZONE/DORMA/DLINE	20.00	Nos	
23/ NS	P/f of floor spring FS 8400 of MAKE OZONE/DORMA/DLINE	1.00	Nos	
24/ NS	OZONE/DORMA/DLINE	6.00	Nos	
25/ NS	P/f of top patch OPF2 of MAKE OZONE/DORMA/DLINE	16.00	Nos	
26/ NS	P/f of over panel side panel connecting patch with pivotOPF 1 of MAKE OZONE/DORMA/DLINE	8.00	Nos	
	OF MAKE OZONE/DORMA/DLINE	1.00	Nos	
28/ NS	P/f of bottom patch OPF3 of MAKE OZONE/DORMA/DLINE	16.00	Nos	
29/ NS	P/f of corner patch lockin with strike plate OPL-1 of MAKE OZONE/DORMA/DLINE	1.00	Nos	
30/ NS	P/f of Glass to glass connector OGC-2 of MAKE OZONE/DORMA/DLINE	16.00	Nos	
	Total			

Contractor