

## BOQ

Turfing of open area in Visitors Hostel

S.No.	Description of item	Qty	Unit	Rate	Amount
1/NS	Providing and laying 50mm thick factory made PCC tiles of M -30 grade made by block making machine with strong vibratory compaction and of approved size and design/ shape laid in required colour and pattern over and including 20-30mm thick compacted bed of course sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. P/101 9/8 gages	185	sqm		
2/NS	Engineer-in-charge Tufted Synthetic Grass Carpet , having pile height 30-40 mm (as approved by Institute), PP+PE yarn type, Denier 11000 DTEX, 12.5 Stitch per 10cm, PP double layer, total weight 250g/sqm,SBR latex coat, appx 100g/sqm with 6mm perforation holes. The weight of tufted must be minimum 1030-1050g/sqm with total weight of 2180-2200 b/sqm all complete as per the direction of Engineer-in-Charge and with 3 year written warranty in form of BG for colour fading. Make- Rossetta/Unitex/Eturf	200	sqm		
	Total				

Contractor