

BOQ

Name of work:: P/F of SS 304 Delay Tank in Academic Block at IISER Mohali

S.No./ DSR	Description of Items	Unit	Qty.	Rate	Amount
1	P/F of Delay Tank made up of SS 304 having thickness 1.5 mm, height 2100mm. 900Mm dia with 75mm dia SS overflow pipe, 75mm dia inlet pipe, lockable cover, 50mm dia pipe sleeves, bends, gate valve, with threaded cover each for sampling and dosing etc. all complete as per the attached drawing & as per the direction of Engineer-in-Charge.	nos	4		
	TOTAL				

Contractor