

## BOQ

Sub: Electric work for Fume Hoods Blowers and Scrubbers motors in various laboratories at IISER Mohali

Sno	Description	Qty	Unit	Rate	Amount
1	Supplying and fixing armoured cable 3x2.5 Sq.mm copper cable on surface etc. as required.				
a)	3 x 2.5 Sq.mm	760	Mtrs.		
2	Supplying and drawing following sizes of FR PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a)	4 x 25 Sq.mm	87	Per Mtr.		
	<b>TOTAL</b>				

Contractor