



INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH MOHALI

(Established by Ministry of Human Resource Development, Govt. of India)
IISER Mohali, Sector-81, Knowledge City, SAS Nagar-140306

Executive Engineer cum Estate Officer

Telefax No. : 0172-2240110

IISER/17-18/EE-EO/

Date: 15.09.2017

To

Sub: Network to discharge storm water near turn (in front of Substations-2) of AB-2 at IISER Mohali, Sector-81, SAS Nagar, Mohali- reg.

Dear Sir,

You are requested to give your competitive rates by 1500 hrs on 20.09.2017 as per the below performa.

Sr. No.	DSR 2014	Description of Items	Qty	Unit	Rate	Amount
1	2.8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
	2.8.1	All kind of soil	2.5	cum		
2	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	4.1.4	1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size)	0.5	Cum		
	4.1.9	1:4:8 (1 cement : 4 fine sand : 8 graded stone aggregate 40 mm nominal size)	1	cum		
3	19.27	Constructing brick masonry road gully chamber 50x45x60 cm with bricks of class designation 75 in cement mortar 1:4 (1 cement : 4 coarse sand) including 500x450 mm pre-cast R.C.C. horizontal grating with frame complete as per standard design :				
	19.27.1	With F.P.S. Bricks	1	Nos		
4	NS	P/f of 6" dia PVC pipe of approved make heavy duty with necessary fittings such as socket, bend, elbow, tee, solution etc with scaffolding all complete at all heights	15	mtr		
5	NS	Refixing of kerb/channel by uprooting the same, leveling the area and jointing with cement mortar 1:2 (1 cement : 2 coarse sand) complete in all respect to the entire satisfaction of the Engineer Incharge.	10	rmt		

GENERAL CONDITIONS OF THE RFQ

1. The rates shall be quoted in the enclosed schedule of quantities and duly signed by the contractor.
2. Rates to be inclusive of all taxes, duties, royalty, GST, etc.
3. Rates to remain firm during the duration of work as well as for the extended period, if any. No escalation in rates will be allowed in any circumstances.
4. The contractor shall comply with all statutory requirements in respect of said work.
5. The quantity can be increase or decrease.
6. The work shall be for the period of ten days to be reckoned from the day of issue of award letter.
7. Penalty of 0.5% per week shall be imposed for delay in work.