

## BOQ

Sr. No.	DSR 2014	Description of Items	Qty	Unit	Rate	Amount
1	2.6	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.				
	2.6.1	All kinds of soil	14	cum		
2	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	4.1.8	1:4:8 (1 cement : 4 fine sand : 8 graded stone aggregate 40 mm nominal size)	1.5	cum		
3	6.1	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in:				
	6.1.1	Cement mortar 1:4 (1 cement : 4 coarse sand)	5	cum		
4	13.1	12 mm cement plaster on the rough side of single or half brick wall of mix :				
	13.1.1	1:4 (1 cement: 4 fine sand)	22.00	sqm		
5	16.3	Supplying and stacking at site.				
	16.3.9	Good earth.	13.00	cum		
6	16.68	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction and of approved size and design/ shape laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with coarse sand etc. all complete as per the direction of Engineer-in-charge.	45.00	sqm		
		Total				
		GST				
		G.Total				

Contractor