

BOQ

Sub: Preparation of clean room surface with epoxy coating in labs

S.No.	Description of item	Qty	Unit	Rate	Amount
1/13.52	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. Complete.				
13.52.2	On concrete work	400	sqm		
2/ 13.80	Providing and applying white cement based putty of average thickness 1mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	60	sqm		
3/ 14.46	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	400	sqm		
	Total				