

BOQ

BOQ

Sr.No.	Description of Item	Qty.	Unit	Rate	Amount
2.8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
2.8.1	All kinds of soil.	0.5	cum		
4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
4.1.2	1:1½:3 (1 Cement: 1½ coarse sand: 3 graded stone aggregate 20 mm nominal size)	0.5	cum		
4.1.8	1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	0.5	cum		
6.4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :				
6.4.2	Cement mortar 1:6 (1 cement : 6 coarse sand)	1.00	cum		
8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills , facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.				
8.2.2	Granite of any colour and shade				
8.2.2.2	Area of slab over 0.50 sqm	8.00	sqm		
8.3	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.				
8.3.2	Granite work	18.00	rmt		
8.6	Mirror polishing on marble work/Granite work/stone work where ever required to give high gloss finish complete.	8.00	sqm		
15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
15.2.2	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	0.50	cum		
15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
15.23.1	For thickness of tiles 10 mm to 25 mm	1.00	sqm		
	TOTAL				

Contractor