

## BOQ

Sr. No.	Description of Items	Qty	Unit	Rate	Amount
16.7	Brick edging in full brick width and half brick depth including excavation, refilling and disposal of surplus earth lead upto 50 metres.				
16.7.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	80	mtr		
16.3	Supplying and stacking at site.				
16.3.9	Good earth	30	cum		
16.68	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	50	Sqm		
	Total				

Contractor