

BOQ

S.No	DSR 2016	Description of item	Qty	Unit	Rate	Amount
1	2.8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m.				
	2.8.1	All kinds of soil.	2	cum		
2	2.27	Supplying and filling in plinth with Jamuna sand under floors, including watering, ramming, consolidating and dressing complete.	2	cum		
3	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	4.1.8	1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	1	cum		
4	6.4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :				
	6.4.1	Cement mortar 1:6 (1 cement : 6 coarse sand)	2	cum		
5	13.1	12 mm cement plaster of mix :				
	13.1.1	1:4 (1 cement: 4 fine sand)	6	sqm		
6	13.41	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade :	6	sqm		
	13.41.1	New work (two or more coats) over and including water tinnable priming coat with cement primer				
7	13.80	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	6	sqm		
8	NS	Providing and installation of SS-304 pipe of 11 mtr height for hoisting of flag having dia of 100 mm (outer pipe) 75 mm dia (intermediate pipe), 48.60 mm dia (inner pipe) including argon welding, firkey for rope, base plate, nut bolts, polishing, etc all complete as per direction of Engineer-in-Charge	115	Kg		
		Total				

Contractor