



भारतीय विज्ञान शिक्षा एवं अनुसंधान संस्थान मोहाली

(मानव संसाधन विकास मंत्रालय का एक स्वायत्त संस्थान, भारत सरकार के अधीन)

सैक्टर-81, नॉलेज सिटी, पो.ओ. मनौली, एस.ए.एस. नगर, मोहाली] पंजाब-140306

INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH MOHALI

(Estd. By Ministry of Human Resource Development, Govt. of India)

Sector – 81, Knowledge City, P.O. Manauli, S.A.S. Nagar, Mohali, Punjab -140 306

Executive Engineer cum Estate Officer

Telefax No. : 0172-2240110

IISER/18-19/EE-EO/

Date: 07.09.2018

Sub: C/o platform for 15KLD STP at IISER Mohali, Sector- 81, SAS Nagar, Mohali- reg.

Dear Sir,

You are requested to give your competitive rates by 1500 hrs on 17.09.2018 as per the below

Sr.No.	Description of Item	Qty.	Unit	Rate	Amount
1/ 2.8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
2.8.1	All kinds of soil.	Cum	4		
2/ 4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
4.1.8	1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	Cum	2		
3/ 4.3	Centering and shuttering including strutting, propping etc. and emoval of form work for :				
4.3.1	Foundations, footings, bases for columns	Sqm	5		
4/ 5.1	Providing and laying in position specified grade of reinforced cementconcrete, excluding the cost of centering, shuttering, finishing andreinforcement - All work up to plinth level :				
5.1.2	1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	2		

5/ 5.2	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :				
5.2.2	1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	2		
6/ 5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
5.22.6	Thermo-Mechanically Treated bars	Kg	400		
	Total				

GENERAL CONDITIONS OF THE RFQ

1. The rates shall be quoted in the enclosed schedule of quantities and duly signed by the contractor.
2. Rates to be inclusive of GST, etc.
3. Rates to remain firm during the duration of work as well as for the extended period, if any. No escalation in rates will be allowed in any circumstances.
4. The contractor shall comply with all statutory requirements in respect of said work.
5. The quantity can be increase or decrease.
6. The work shall be for the period of three weeks to be reckoned from the day of issue of award letter.
7. EMD amounting to Rs.1,400/- in favour of Registrar IISER, Mohali payable at Mohali.
8. Penalty of 0.5% per week shall be imposed for delay in work.

Sd/-
Executive Engineer