

BOQ

S.no.	DSR	Description	Qty	Unit	Rate	Amount
1	10.25	Cleaning of RCC tank by dewatering & External/Internal washing, sludge removal, algae removal with anti bacterial treatment, vaccum cleaning & UV treatment to make it one time bacteria free as per the below mentioned procedure for cleaning.				
	a	Underground	1405000.00	ltr		
		Total				

Contractor

Procedure for Cleaning

- 1 External washing and dewatering
- 2 Sludge removal
- 3 Algae removal
- 4 Internal washing
- 5 Anti bacterial treatment
- 6 Vaccum cleaning
- 7 UV treatment