

**BOQ**

SUB: Shifting of fire fighting line, water supply lines and cables from the INST land at IISER Mohali”.

S.no.	DSR	Description	Qty	Unit	Rate	Amount
1	2.8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
	2.8.1	All kinds of soil	430	cum		
2	NS	P/f of 100 mm Class C Heavy duty MS pipe of Make Tata/Jindal	20	mtr		
3	NS	P/f of 100 mm dia Class C heavy duty bend of Make Jindal/Tata	4	Nos		
4	NS	P/f of Electrical Control Busbar Panel outdoor type with 600 Amp al Busbar of size 800x600x250 mm 2mm CRC sheet with powder coated MS angle frame	2	Nos		
		Total				

Contractor