

BOQ

Sr. No.	Description of Items	Qty	Unit	Rate	Amount
1/ 10.16	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.				
10.16.1	Hot finished welded type tubes	760.00	Kg		
2/ 12.47	Providing & fixing UV stabilised fiberglass reinforced plastic sheet roofing up to any pitch, including fixing with polymer coated 'J' or 'L' hooks, bolts & nuts 8mm dia. G.I plain/bitumen washers complete but excluding the cost of purlins, rafters, trusses etc. The sheets shall be manufactured out of 2400 TEX panel rovigs incorporating minimum 0.3% ultra-violet stabiliser in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to IS 10192 and IS 12866. The sheets shall be opaque or translucent, clear or pigmented, textured or smooth as specified.				
12.47.2	2 mm thick flat	80.00	sqm		
3/13.61	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
13.61.1	Two or more coats on new work	40.00	sqm		
	Total				

Contractor