

Sheet2
BOQ

S.No.	Description of item	Qty	Unit	Rate	Amount
1	Cleaning of Rain water harvesting wells, 4 mtr (appx) deep in closed area by using manual labour & Air compressor (pressure upto 5kgper cm sq) along with suitable capacity suction pump to remove stagnant water/slush, with adequate labours all complete including testing, taking all precautionary steps to prevent the labour from being injured to increase the efficiency of RWH well to the desired levels.	17	Nos		
	Total				

Contractor