

## BOQ

**BOQ**

S No	Item	Qty	Unit	Rate	Amount
1	Servicing of Air Cooled package unit of Lecture Hall Building having capacity 11.5 TR- 15 nos, 16.5 TR- 5 nos unit, 5.5 TR-01 no unit (Total 260.50 TR) including outdoors, condensor coil and indoor units cooling coils, cleaning with coil shine or other approved chemical, checking of pully and its replacement, fan allignment, electrical connection checking and remedies of defect, Air filter cleaning, faulty PCB replacement, refrigerant pressure checking of each unit, refrigerant topping with gas R-22, leakage testing, V belts tightening, replacement of broken belt, blower and outdoor motors bearing greasing, all complete as per direction of Engineer-in-Charge.	1	Job		
2	Servicing of Air Conditioning system Water Cooled package unit of CAF having capacity 16.5 TR- 3 nos unit (Total 49.50 TR) including water cooled condensor descaling and indoor units cooling coils, cleaning with coil shine or approved chemical, checking of pully and its replacement, fan allignment, electrical connection checking and remedies of defect, Air filter cleaning, refrigerant pressure checking of each unit, refrigerant topping with gas R-22, leakage testing, V belts tightening, replacement of broken belt, blower and outdoor motors bearing greasing.	1	Job		
	Total				

Contractor