

## BOQ

Sr. No.	Description of item	Qty	Unit	Rate	Amount
1	Providing and inserting 12mm dia galvanised steel injection nipple in honey comb area and along crack line including drilling of holes of required diametre (20mm to 30mm) up to depth from 30mm to 80mm at required spacing and making the hole & crack dust free by blowing compressed air, sealing the distance between injection nipple with adhesive chemical of approved make and allow it to cure complete as per direction of Engineer-In-Charge.	50	Nos		
2	Providing & Applying polymer modified water proofing coating with elastic non shrink waterproofing compound (rain tight and non shrink powder) on floor in two coats one coat of self priming of cementitious waterproofing polymer(dilution with water in the ratio of 1:1) after scrapping and properly cleaning the surface to remove pre-existing paint film & loose particles till plaster is visible, complete in all respect as per the direction of Engineer-in-Charge.	165	sqm		
	Total				

- 1 Clean the surface area with wire brush
- 2 Wet the area before coating
- 3 Apply first coat with stiff brush with chemical
- 4 Apply second coat after 5-6 hours with chemical
- 5 Grouting with 3" PVC nozzle non shrinking powder by using force rock chemical where required

Contractor