

BOQ

Sub: Preparation of Labs in AB1,2 etc at IISER Mohali.

Sr.no	Description of Item	Qty.	Unit	Rate	Amount
1/1.17	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required. Make: Polycab, Havells, KEI,Finolex.				
1.17.30	3 X 6 Sq. mm	900	mtrs		
2/1.24	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.Make : ABB,L& T,Anchor Roma				
1.24.3	15/16 amp switch	16	nos		
1.24.5	6 pin 15/16 amp socket outlet	16	nos		
3/NS	Supplying and Fixing PVC batten/flexible pipe on the wall with base i/c. accessories etc. as required.				
a)	1" to 1.25"	80	mtrs		
4/NS	Supplying and Fixing following size PVC modular box as required, Make: ABB,L&T,Anchor Roma,Greatwhite				
a)	6 Module	8	nos		
5/1.28	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.Make: ABB,L&T,Anchor Roma,Greatwhite				
1.28.4	6 Module	8	nos		
6/2.10	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.Make : ABB/Schneider/Havells				
2.10.1	Single pole	4	each		
7/NS	Supplying and fixing 63 amps rating, 240/415 volts, 10kA,"C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Make : ABB/Schneider/Havells				
a)	Double pole	2	nos		
8/NS	Supplying and fixing DP sheet steel enclosure on surface/ recess.Make : ABB,Schneider,Indo Asian,Havells	2	each		
	Total				

Contractor