

## BOQ

S. No	Description of item	Qty	Unit	Rate	Amount
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
	For thickness of tiles 10 mm to 25 mm	15	sqm		
2	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	40	sqm		
3	Providing and laying tactile tile (for vision impaired persons as per standards) of size 300x300x9.8mm having with water absorption less than 0.5% and conforming to IS:15622 of approved make in all colours and shades in for outdoor floors such as footpath, court yard, multi modals location etc., laid on 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigments etc. complete as per direction of Engineer-in-Charge.	55	sqm		
	Total				

Contractor