

BOQ

S. No	Description of item	Qty	Unit	Rate	Amount
15.23	P/f of 3-4 mm ACP sheet (single side decorative) on walls, ceiling with screws to seal it proper by filling silicon all complete as per direction of Engineer-in-Charge of Make ALSTRONG/ ALEX PANELS/ ALUCOBOND/ VIVA/ EUROBOND	140	sqm		
	Total				

Contractor