

-

BOQ

Sub: Preperation of cricket pitch at Sports Complex in IISER mohali

S.No.	Discription of item	Qty	Unit	Rate	Amount
1/ 2.1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth upto 50 m and lift upto 1.5 m, disposed soil to be levelled and neatly dressed :				
2.1.1	All kinds of soil	27	cum		
2/ 2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	4	cum		
3/ 2.27	Supplying and filling in plinth with Jamuna sand under floors including, watering, ramming consolidating and dressing complete.	6	cum		
4/ NS	Supply and filling in pitch with black soil, including watering, ramming, consolidating and dressing complete.	22	cum		
	Total				

Contractor