

BOQ

Sub: Modification in lab of Dr. A.K. De

Sr. No.	Discription of Items	Qty	Unit	Rate	Amount
N.S/1	P/f of 3mm PVDF ACP sheet in walls & ceilings with screws to seal it proper all complete as per direction of Engineer-in-charge.	140	sqm		
NS/2	P/f of 3mm PVDF ACP sheet in partitions with neoprene all complete as per direction of Engineer-in-charge.	35	sqm		
21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
21.1.1	For fixed portion				
21.1.1.2	Powder coated aluminium (minimum thickness of powder coating 50 micron)	150.00	kg		
21.1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of PVC / neoprene gasket required (Fittings shall be paid for separately).				
21.1.2.2	Powder coated aluminium (minimum thickness of powder coating 50 micron)	70.00	kg		
	Total				

Contractor