

BOQ

BOQ

Sub: Painting work in Hostel No. 5&7 & Duplex houses.

S.No.	Discription of item	Qty	Unit	Rate	Amount
1/ 13.80	Providing and applying white cement based putty of average tickness 1mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	250	sqm		
2/ 13.41	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :				
13.41.1	New work (two or more coats) over and including priming coat with cement primer. (Execulded putty).	250	sqm		
3/ 14.45	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :				
14.45.1	Old work (one or more coats)	40750	sqm		
4/ 14.46	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	250	sqm		
5/ 14.53	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade :				
14.53.1	One or more coats on old work.	6700	sqm		
6/ 14.54	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
14.54.1	One or more coats on old work.	19300	sqm		
7/ 14.65	Finishing walls with textured exterior paint of required shade :				
14.65.2	Old work (One or more coats) applied @ 1.82 ltr/10 sqm.	7500	sqm		
	Total				

Contractor