

BOQ

Sub : Installation of exhaust system in LHC - reg.

S.No.	Description of Item	Qty.	Unit	Rate	Amount
1	Supply, fabrication, installation and testing of 24G sheet metal ducts (factory fabricated), all complete as per the direction of Engineer in charge.	80	Sqm		
2	P/f of exhaust fan metal type fan speed of 1400 rpm, 18" size, double bearing. Make : BAJAJ/KHAITAN/CG.	4	Nos.		
3	P/f of armoured copper conductor, 1.5 sq mm, 3 core cable of reputed brand with saddle for connection to fan. MAKE POLYCAB/BONTTON/HAEVELLS	100	mtrs		
4	P/I of GI exhaust hood all complete of size 8'x2' with grills	1	Nos		
5	P/I of GI exhaust hood all complete of size 3'x2' with grills	1	Nos		
6	Dismanteling of wall, repair the edges, painting the same	1	Job		
	Total				

Contractor