

BOQ

Sub- Car parking in Admin. Block at IISER Mohali.

| S.No. | DSR 2014 | Description of item | Qty | Unit | Rate | Amount |
|-------|----------|--|------|------|------|--------|
| 1 | 2.8 | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. | | | | |
| | 2.8.1 | All kinds of soil. | 1 | cum | | |
| 2 | 4.1 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : | | | | |
| | 4.1.2 | 1:1½:3 (1 Cement: 1½ coarse sand: 3 graded stone aggregate 20 mm nominal size). | 1.5 | cum | | |
| 3 | 10.16 | Steel work in built up tubular trusses including cutting, hoisting fixing in position and applying a priming coat of approved steel primer, welded and bolted including special shaped washers etc. complete. | | | | |
| | 10.16.1 | Hot finished welded type tubes. | 1450 | kg | | |
| 4 | 13.61 | Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : | | | | |
| | 13.61.1 | Two or more coats on new work | 70 | sqm | | |
| 5 | NS | Providing and fixing of 6mm polycarbonate multiwall white/coloured sheet of Make LEXAN/ DANPAUL or equivalent including Aluminum dome section and EPDM rubber bottom and top all complete as per direction of Engineer-in-Charge | 150 | sqm | | |
| | | Total | | | | |

Contractor