

-

BOQ

Sub: P/a of epoxy coating of modular STP's

S.No.	Description of item	Qty	Unit	Rate	Amount
1/13.52	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. Complete.				
13.52.1	On steel work	350	sqm		
13.52.2	On concrete work	200	sqm		
2/ 13.55	Painting (two or more coats) on rain water, soil, waste and vent pipes and fittings with black anticorrosive bitumastic paint approved brand and manufacture over and including a priming of ready mixed zinc chromate yellow primer :				
13.55.1	100 mm diameter pipes	100	mtr		
13.55.2	150 mm diameter pipes	100	mtr		
	Total				

Contractor