

**BOQ**

Sub: P/F of Delay Tank for Radio Active Lab at IISER Mohali.

Sr. No.	Description	Qty	Unit	Rate	Amount
1	P/F of Delay Tank made up of SS 304 having thickness 2.5mm, height 2100mm, 900mm dia with 75mm dia SS overflow pipe, 75mm dia inlet pipe, lockable cover, 50mm dia pipe sleeves with threaded cover each for sampling and dosing etc. all complete as per the direction of Engineer-in-Charge (Drawing attached). CPVC Piping work to be measured separately.	2	Nos.		
	TOTAL				

Contractor