

BOQ					
Sub- Electrical and piping work for Deep Tube well					
Sr. No.	Description of Items	Qty	Unit	Rates	Amount
1	Supply of Erection of Submersible Pump 41 HP 5 Stage Make KSB.	1	No		
2	Supply of Erection of GI Pipe 3" B Class Make Jindel with flung. Nut bolt & gasket.	250	Feet		
3	Supply & laying of Submersible cable 3 core 10mmsq Make Finolex	180	Mtr		
4	Erection of Submersible Feeder Piller Stater 41 HP Start delta with I/C MCCB 100Amp.	1	No		
5	Supply & laying of Main Cable for Submersible Pump 3.5 X 35mmsq Make Havel with excavation back filling, bricks & sand.	50	Mtr		
6	Supply of Erection of GI Earth Pit as per IS 3043 with Char coil main-hole cover watering pipe etc.	2	No		
	Total				

Contractor