

BOQ

Sub:Water Proofing in Dr.Goutam Sheet Lab.

Sr. No.	Specification	Qty	unit	rate	amount
1	Drilling the holes in RCC/ Brick work of 12mm dia and fixing the nozzles with quick setting component.				
	Inserting the cement slurry admixed with NSPG or Equivalent component with pressure of 10kg/cum into the nozzles				
	After grouting with pump, removing the nozzles filling providing & applying two coats of Non-Magnetic water proof coating of "BOSTIIC 10"/ or Equivalent on the entire area of Pit.	1150	sqft		
2	Providing & fixing of Kota Stone 18-19mm thick of size 2'x2' on the face of water proofing treatment from inside and proofing water pouring cement slurry to make the surface completely water proof.	800	sqft		
	Total				

Contractor