

**BOQ**

**Sub: Preparation of Footpath approaching Lecture Hall to Academic Block-1 at IISER, MOHALI.**

S. No	Description of Items	Unit	Qty	Rate	Amount
1/ 2.28	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m.				
2.28.1	All kinds of soil.	284	sqm		
2/ 16.2	Extra for compaction of earth work in embankment under optimum moisture conditions to give at least 95% of the maximum dry density (proctor density).	200	cum		
3/ 23.8	Spreading of sludge, dump manure or/and good earth in required thickness (Cost of sludge, dump manure or/ and good earth to be paid separately).	200	cum		
4/NS	Brick edging laid height-wise with half brick depth including excavation, refilling and disposal of surplus earth lead upto 50 metres :				
	With common burnt clay F.P.S. bricks of class designation 7.5	240	metre		
5/ NS	Providing and laying 75mm thick factory made cement concrete interlocking paver of M-30 grade made by block making machine with string vibratory compaction and of approved size and design/shape laid in required colour and patternover and including 50 mm thick compacted bed of course sand. Filling the joints with coarse etc. all complete as per the direction of Engineer-in-charge (MAKE-N.T.C.).	435	sqm		
6/ NS	Cost of carriage of good earth including loading, unloading & stacking for 100m lead (Derived from DSR item no. 1.2.2)..	200	cum		
	Total				

Contractor